



July 2, 2024

Kevin Wise  
Chairman, Carlisle Baptist Church Building Committee  
835 South Berthe Avenue  
Panama City, Florida 32404

Reference: addendum no. 1  
Carlisle Baptist Church rebuild - Phase 1  
Panama City, Florida

### Addendum no. 1

1. Clarification: Sheet A34, Countertops; quartz countertops are required throughout in phase 1.
2. Clarification: Sheet A34, Cabinet door panels; provide flat panel cabinet doors finished to match cabinets.
3. Clarifications: Sheet A31, Women 105 and Men 111; provide knee braces at 3' o.c. maximum.
4. Clarification: Steeple; Campbellsville Industries, Inc. M-series model M-410 39'-6".
5. Clarification: Sheet A19, keynote 14; The stained oak panels shall be 3/4" oak plywood with 1/2" X 3" trim at corners and joints, stain color selected by architect.
6. Clarification: Sheets A8/A25, door no. S104.1 shall be a single door.
7. Clarification: Sheets A8, A12, A25 and A26, door no.'s S114.1, S114.2, S114.3, S114.4, S114.5, S114.6, E137.1, E137.2, E137.3, E137.4, E137.5, E137.6, and E115.2 shall receive door closers. Storefront doors shall receive LCN 4040 XP door closers.
8. Clarification: floor and wall stage pocket boxes; floor and wall stage pocket boxes shall be provided and installed by others.
9. Clarification: low voltage cables and connectors; low voltage cables and connectors shall be provided and installed by others.
10. Clarification: see number 9, above.
11. Clarification: sanctuary fire alarm; The sanctuary fire alarm does not tie into the existing building.
12. Clarification: Carpet; The carpeting shall be tiles, 24" x 24".
13. Clarification: Ceramic Tile; All ceramic tile shall be Tile 1.
14. Clarification: 6" and 8" metal stud framing; See attached addendum no. 1, drawing no. 1 for 6" and 8" metal stud framing designations.
  - a. 1/2" gypsum board is required on the walls.
  - b. sound attenuation batts are required in the interior walls.
15. Clarification: Phase 1 and Phase 2 connection details will be provided when phase 2 construction commences.
16. Clarification: The split system heat pump is for phase 1.
17. Clarification: Storefront door/windows; The storefront shall be clear anodized finished, as indicated in the door schedule, with grey PPG solar ban 70 glazing, color to be selected by architect. All exterior glazing shall be impact resistant.
18. Clarification: Door hardware; Door hardware shall be Schlage.
19. Clarification: Sheet A19, keynote 7; Keynote 7 should read, suspended acoustical tile.
20. Clarification: Sheet A19, keynote 17; Keynote 17 should read, relocated faceted glass window.

21. Clarification: There will be no separate specification/project manual.
22. Clarification: Sheet E3, note 22; The projector locations referred to in note 22 are for suspended projectors, located at the ceiling level, provided and installed by others.
23. Clarification: Sheets A12 and A26, Storefront exit doors; All storefront exit doors shall receive panic hardware.
24. Clarification: Storefront; All aluminum storefront shall be thermally broken with 1" insulating PPG grey solar ban 70 glazing, color selected by architect.
25. Clarification: roofing; The metal building manufacturer will be responsible for providing the necessary substrate for attaching the metal roofing while complying with the code imposed, wind load requirements.
26. Change: Sheet A14, Second Floor Plan - Education Building; See Addendum no. 1, Drawing no. 2 for changes to Backlight Room.
27. Add: Sheet A14, Second Floor Plan - regarding electrical - add one light fixture type G controlled by a wall mounted occupancy sensor and connect to the light circuit serving E-206. In the same room add a duplex receptacle and connect to the circuit serving the receptacle in E-206.

Thank you for your consideration and please call if you have any questions regarding this matter.

Sincerely,

***Mark Mercer & Associates, Inc.***

**Mark Mercer**

Mark Mercer, NCARB